



BARRAS DE COBRE

		Intensidade Nominal (Amperes)							
		Temp. Trabalho 85° C				Temp. Trabalho 65° C			
Dimensões Larg x Esp	Peso Kg / Mt	I	II	III	IIII	I	II	III	IIII
15 x 3	0,700	216	376	480		162	282	361	
20 x 3	0,560	272	464	574		204	348	431	
25 x 3	0,670	326	549	664		245	412	498	
30 x 3	0,800	380	634	752		285	476	564	
40 x 3	1,08	488	800	920		366	600	690	
15 x 5	0,700	289				218			
20 x 5	0,920	363	665	920		274	500	690	
25 x 5	1,140	433	776	1060		327	586	795	
30 x 5	1,360	502	890	1187	1329	379	672	896	1003
40 x 5	1,800	639	1108	1444	1617	482	836	1090	1220
50 x 5	2,260	772	1317	1670	1870	583	994	1260	1411
60 x 5	2,700	912	1524	1908	2137	688	1150	1440	1613
80 x 5	3,600	1173	1921	2319	2597	885	1450	1750	1960
100 x 5	4,500	1461	2292	2716	3042	1080	1730	2050	2296
125 x 5	5,640	1723	2679	3155	3532	1300	2022	2381	2666
20 x 10	1,800	564	1100	1573		427	825	1180	
30 x 10	2,700	756	1300	1701		573	986	1289	
40 x 10	3,600	944	1624	2124		715	1230	1609	
50 x 10	4,500	1129	2001	2703		852	1510	2040	
60 x 10	5,400	1305	2279	3048		985	1720	2300	
80 x 10	7,200	1643	2796	3697		1240	2110	2790	
100 x 10	9,000	1974	3286	4320		1490	2480	3260	
120 x 10	10,800	2306	3790	4956		1740	2860	3740	
160 x 10	14,400	2942	4757	6201		2220	3590	4680	
200 x 10	18,000	3564	5711	7433		2690	4310	5610	

Temperatura ambiente dentro do armário 35° C

Temperatura de trabalho medida na barra de cobre, conforme Norma DIN 43671



Casa Félix, Lda.

Parque Empresarial Granja-Vialonga, Arm.30
2625-607 VIALONGA

www.casafelix.pt

Tel.: 218 483 380

Fax: 218 484 531